

PREFABRICATED SOLUTIONS FOR PEAK PRODUCTIVITY

Prefabrication Services CP 680



With the increase market demands on projects like shorter project schedules, on-site space limitations, social distancing requirements, and constraints on budgets require a solution to help with productivity across your workflow.

Hilti's customized Prefab Service CP 680 offers ready to use firestop sleeves for your projects. Create openings with the firestop already included, no more time wasted in the shop or onsite adjusting sleeve heights and assembling parts and pieces. All you need to know is the diameter, height, type of piping, and water requirements, and we'll create the customized solution for your project. Help boost your productivity with the right firestop sleeve ready to install — so you stay on schedule and budget.

APPLICATIONS AND ADVANTAGES

- Concrete slabs built with traditional formwork or metal decking
- New building construction
- Sealing metal, plastic pipes and electrical conduits in concrete floors up to 4 hours
- Can be used in concrete slabs from 2-1/2" and above
- Quick and simple installation — designed to increase your productivity and reduce labor costs
- Peace of mind — cast-in devices remove scope for errors compared to traditional firestopping of vertical penetrations
- Creates an opening with the firestop already included — no coring or coming back for firestopping required
- Integrated moisture and smoke seal — no additional backfilling required

Get Productive with Prefabricated Solutions

