



## System No. F-A-3092



CAN/ULC S115
F Rating — 3 Hr
FT Rating — 0 and 1/2 Hr (See Item 3)
FH Rating — 0 and 3 Hr (See Item 3
FTH Rating — 0 and 1/2 Hr (See Item 3)





- 1. Floor Assembly Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete.
- 2. Firestop Device\* Cast in place firestop device with optional accessories including sleeve extension permanently embedded during concrete placement in accordance with accompanying installation instructions.
  - HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC CFS-CID U 2", CFS-CID U 2" CA
- 3. Cable One nom 4/C, 500 kcmil copper or aluminum conductor PVC jacketed aluminum clad or steel clad TEK cable installed concentrically within device. Cable to be rigidly supported on both sides of floor assembly.
- \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

