


System No. F-A-3092

ANSI/UL1479 (ASTM E814)	
F Rating — 3 Hr	
T Ratings — ½ Hr	

SECTION A-A

TOP VIEW



- $1.\ Floor\ Assembly --\ Min\ 4-1/2\ in.\ (114\ mm)\ thick\ reinforced\ lightweight\ or\ normal\ weight\ (100-150\ pcf\ or\ 1600-2400\ kg/m3)\ concrete.$
- 2. Firestop Device* Cast in place firestop device with optional accessories including sleeve extension permanently embedded during concrete placement in accordance with accompanying installation instructions.
 - HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC CFS-CID U 2", CFS-CID U 2" CA
- 3. Cable One nom 4/C, 500 kcmil copper conductor PVC jacketed aluminum clad or steel clad TEK cable installed concentrically within device. Cable to be rigidly supported on both sides of floor assembly.
- * Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

